



1 DATA CONNECTION TO EQUIPMENT PANELS
 UP TO 120V

DETAIL KEY NOTES

- ① EQUIPMENT PANEL, CONTRACTOR FURNISHED CONTRACTOR INSTALLED (CFCI)
- ②A 1" CONDUIT TO NEAREST CABLE TRAY, BONDED, GROUNDED TO TRAY, WITH BUSHING AND PULL STRING, CFCI
- ②B 1" CONDUIT TO THE HEIGHT OF EXISTING J-HOOKS WITH BUSHINGS AND PULL STRING, CFCI
- ③ SURFACE MOUNTED BISCUIT JACK OR DATA OUTLET AND NETWORK CABLE S (HORIZONTAL AND PATCHES) BY MCIT